

The Lotis Engineering Group, P.C.

5465 Transit Road – Suite 23
East Amherst, New York 14051-2232
716.276.8707

March 14, 2017

Jamie Phillips
Lancaster Central School District
177 Central Avenue
Lancaster, New York 14086

Re: Lead Testing in School Drinking Water
Lancaster District Offices
177 Central Ave,
Lancaster, NY 14086

Dear Ms. Phillips:


On September 6, 2016, Governor Andrew M. Cuomo signed legislation (S.8158/A.10740) mandating that public schools in New York State test potable water for lead contamination. The New York State Department of Health (NYSDOH) also issued emergency regulations pursuant to the new legislation (NYCRR Title X, Subpart 67-4).

In accordance with the new law and regulations, Lancaster Central School District (District) contracted The Lotis Engineering Group, P.C. (Lotis), to complete water testing in all District buildings. This submission summarizes the analytical results of sampling completed on February 24, 2017 at the Lancaster District Offices.

Maintenance closets and showers are not required to be tested under the new state mandates and were not included under this scope of work. Per the emergency regulations issued by the NYSDOH, first-draw samples were collected from cold water outlets after water lay motionless in the pipes for a minimum of 8 hours, but not more than 18 hours. The school district was responsible for flushing outlets at least 8 hours prior to sample collection. Lotis was notified by the school district that flushing was completed over 8 hours prior to sampling. However, this could not be independently verified by Lotis.

Samples were collected by placing a sterile container under each outlet and turning on the water source, allowing Lotis to collect a first-draw cold water sample. Samples were collected in clean 250 mL containers containing the appropriate nitric acid preservative, as provided by the testing laboratory. Samples were then delivered to Microbac Laboratories (a certified Environmental Laboratory Approved Program) following standard chain of custody protocols.

A total of one outlet was sampled inside the building during the resample event.



The Lotis Engineering Group, P.C.

6465 Transit Road – Suite 23
East Amherst, New York 14051-2232
716.276.8707

At the Lancaster District Offices, 1 sample exceeded the 15 parts per billion (ppb) action level set forth by the NYSDOH. A summary of this sample is included in the following table:

Table 1 – Samples Exceeding 15 ppb

Sample ID	Location Details	Results (ppb)
1-District Office Maintenance Shop sink	Maintenance Room- Sink	45.3

Included in this submission are the complete laboratory analytical reports, chain of custody logs and photos of sample locations that exceeded the action levels.

In accordance with the new legislation, use of the aforementioned outlets is prohibited until a lead remediation plan is implemented and new testing demonstrates that the resulting lead levels are below 15 ppb. Alternative water supplies may be necessary in impacted areas. The legislation requires that Lancaster Central School District provide these results to the NYSDOH within one business day of receipt. Further, notification to building staff, all persons in parental relation to students, the local health department and the State Education Department is required within 10 business days of receipt of these results. These results and any associated remedial plans must be posted on the District's website within six weeks of receipt and all records must be retained by the District for at least 10 years.

The NYSDOH recommends reviewing "3Ts for Reducing Lead in Drinking Water in Schools, Revised Technical Guidance" published by the United States Environmental Protection Agency (USEPA) to assist schools in assessing an appropriate remediation plan. A copy of this publication can be reviewed through the following hyperlink [3Ts for Reducing Lead in Drinking Water in Schools](#).

Lotis is available at your convenience to discuss this issue further.

Sincerely,



Kelly Reidy
Environmental Scientist



David N. Robinson, P.E.
President/CEO



March 3, 2017

The Lotis Engineering Group, P.C.
6465 Transit Road - Suite 23
East Amherst, NY 14051-2232

Work Order No.: 17B1458

Re: District Office

Dear Kelly Reidy:

Microbac Laboratories, Inc. - Chicagoland Division received 1 sample(s) on 2/28/2017 9:50:00AM for the analyses presented in the following report as Work Order 17B1458.

The enclosed results were obtained from and are applicable to the sample(s) as received at the laboratory. All sample results are reported on an "as received" basis unless otherwise noted.

All data included in this report have been reviewed and meet the applicable project specific and certification specific requirements, unless otherwise noted. A qualifications page is included in this report and lists the programs under which Microbac maintains certification.

This report has been paginated in its entirety and shall not be reproduced except in full, without the written approval of Microbac Laboratories.

We appreciate the opportunity to service your analytical needs. If you have any questions, please contact your project manager. For any feedback, please contact Donna Ruokonen, Managing Director, at donna.ruokonen@microbac.com.

Sincerely,
Microbac Laboratories, Inc.

A handwritten signature in black ink, appearing to read "Karen Ziolkowski", with a long horizontal line extending to the right.

Karen Ziolkowski
Senior Project Manager

**WORK ORDER SAMPLE SUMMARY****Date:** *Friday, March 3, 2017***Client:** The Lotis Engineering Group, P.C.**Project:** District Office**Lab Order:** 17B1458

Lab Sample ID	Client Sample ID	Tag Number	Collection Date	Date Received
17B1458-01	1-District Office Maintenance Shop		02/24/2017 07:08	2/28/2017 9:50:00AM



Analytical Results

Date: Friday, March 3, 2017

Client: The Lotus Engineering Group, P.C.
Client Project: District Office

Work Order: 17B1458
Received: 02/28/2017 9:50

Analyses	Certs	Result	Units	Qual	Analyzed	Tech	Method
01	1-District Office Maintenance Shop sink						Collected: 02/24/2017 07:08
Lead	gdmnoi	45.3	ug/L		03/02/2017 13:16	SJE	EPA 200.8 Rev 5.4

Microbac Laboratories, Inc.

250 West 84th Drive | Merrillville, IN 46410 | 800.536.8379 p | 219.769.8378 p | 219.769.1664 f | www.microbac.com



FLAGS, FOOTNOTES AND ABBREVIATIONS (as needed)

B = Detected in the associated method Blank at a concentration above the routine RL
b = Detected in the associated method Blank at a concentration greater than 2.2 times the MDL
b* = Detected in the associated method Blank at a concentration greater than half the RL
CFU = Colony forming units
D = Dilution performed on sample
DF = Dilution Factor
g = Gram
E = Value above quantitation range
H = Analyte was prepared and/or analyzed outside of the analytical method holding time
I = Matrix Interference
J = Analyte concentration detected between RL and MDL (Metals / Organics)
LOD = Limit of Detection
LOQ = Limit of Quantitation
m3 = Meters cubed
MDL = Method Detection Limit
mg/Kg = Milligrams per Kilogram (ppm)
mg/L = Milligrams per Liter (ppm)
NA = Not Analyzed
ND = Not Detected at the Reporting Limit (or the Method Detection Limit, if used)
NR = Not Recovered
R = RPD outside accepted recovery limits
RL = Reporting Limit
S = Spike recovery outside recovery limits
Surr = Surrogate
U = Undetected
> = Greater than
< = Less than
% = Percent
* = Result exceeds project specific limits

ANALYTE TYPES: (AT)

A,B = Target Analyte
I = Internal Standard
M = Summation Analyte
S = Surrogate
T = Tentatively Identified Compound (TIC, concentration estimated)

QC SAMPLE IDENTIFICATIONS

BLK = Method Blank	ICSA = Interference Check Standard "A"
DUP = Method Duplicate	ICSAB = Interference Check Standard "AB"
BS = Method Blank Spike	BSD = Method Blank Spike Duplicate
MS = Matrix Spike	MSD = Matrix Spike Duplicate
ICB = Initial Calibration Blank	ICV = Initial Calibration Verification
CCB = Continuing Calibration Blank	CCV = Continuing Calibration Verification
CRL = Client Required Reporting Limit	OPR = Ongoing Precision and Recovery Standard
PDS = Post Digestion Spike	SD = Serial Dilution
QCS = Quality Control Standard	

CERTIFICATIONS (Certs)

Below is a list of certifications maintained by the Microbac Merrillville Laboratory. All data included in this report has been reviewed for and meets all project specific and quality control requirements of the applicable accreditation, unless otherwise noted. Complete lists of individual analytes pursuant to each certification below are available upon request.

- ^d Illinois EPA drinking water, wastewater and solid waste analysis (#200064)
- ^g Indiana SDH chemical analysis of drinking water (#C-45-03)
- ⁱ Kansas Dept Health & Env. NELAP (#E-10397)
- ^m New York State Department of Health Wadsworth (#12006)
- ⁿ Pennsylvania Department of Environmental Protection (#68-04863)
- ^o Virginia Department of General Services Division of Consolidated Laboratory Services (#7990)



COOLER INSPECTION

Client Name: The Lotis Engineering Group, P.C.

Date: Friday, March 3, 2017

Date/Time Received: 02/28/2017 09:50

Work Order Number: 17B1458

Received by: Samantha Paulus

Checklist completed by: 2/28/2017 11:06:00AM | Samantha Paulus

Reviewed by: 2/28/2017 | KAZ

Carrier Name: UPS

Cooler ID: Default Cooler

Container/Temp Blank Temperature: 15.4° C

After-Hour Arrival?

Shipping container/cooler in good condition?

Custody seals intact on shipping container/cooler?

Custody seals intact on sample containers?

COC present?

COC included sufficient client identification?

COC included sufficient sample collector information?

COC included a sample description?

COC agrees with sample labels?

COC identified the appropriate matrix?

COC included date of collection?

COC included time of collection?

COC identified the appropriate number of containers?

Samples in proper container/bottle?

Sample containers intact?

Sufficient sample volume for indicated test?

All samples received within holding time?

If the samples are preserved, are the preservatives identified?

Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>	
Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	Not Present <input type="checkbox"/>
Yes	<input type="checkbox"/>	No	<input type="checkbox"/>	Not Present <input checked="" type="checkbox"/>
Yes	<input type="checkbox"/>	No	<input type="checkbox"/>	Not Present <input checked="" type="checkbox"/>
Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Yes	<input checked="" type="checkbox"/>	No	<input checked="" type="checkbox"/>	
Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>	
Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>	

If No, adjusted by? _____

COC included the requested analyses?

COC signed when relinquished and received?

Samples received on ice?

Samples properly preserved?

Voa vials for aqueous samples have zero headspace?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>	
Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>	
Yes	<input type="checkbox"/>	No	<input type="checkbox"/>	No VOA vials submitted <input checked="" type="checkbox"/>

Cooler Comments:

ANY "NO" EVALUATION (excluding After-Hour Receipt) REQUIRES CLIENT NOTIFICATION.

Sample ID	Client Sample ID	Comments
17B1458-01	1-District Office Maintenance Shop sin	

Microbac Laboratories, Inc.

250 West 84th Drive | Merrillville, IN 46410 | 800.536.8379 p | 219.769.8378 p | 219.769.1664 f | www.microbac.com

17B1458

SampleID	Matrix	SampleName	SampleAlias	Sampled	SampledBy
1	Aqueous				

x Matthew Sam

2/24/2017

950
Remanished to UPS

15.4
- 0 NT
15.4°

rec @ lab by James Fawley
2-28-17

